

Subdivisions Tp. 1 S., R. 33 E. W.M.

Chains		Feet
	$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; raised mound of stone and earth, $1\frac{1}{2}$ ft. high and $3\frac{1}{2}$ ft. base over Cor., on N.W. face of hill. Pits impracticable.	
41.75	Draw, course N.W. Ascend.	
43.50	Summit of ridge falls N.E. Descend steep stony hill.	+300
48.55	Deep canyon, 400', course N.E. Ascend.	
77.25	Gibson Gulch, course N.W. "	
80.50	The Cor. to Secs. 29, 30, 31 & 32. Land; mountainous, 81.50 chs. No timber. Soil; 4th rate. Good grass on N. slopes.	
W. bet. Secs. 30 & 31.		
Var. $19^{\circ} 15'$ E.		
Ascend.		
4.00	Summit of ridge falls N. Descend.	
6.50	Head of canyon, course N. Ascend.	
8.19	Top of ridge falls N. Enter field, fence, course N.E. & S.W. Descend.	
Sept. 12, 1890.		
20.20	Deep ravine, with thick brush, course N. Ascend.	
29.90	Leave field.	
35.50	Summit falls N. Descend.	
40.00	Set basalt stone, 18 x 10 x 4 ins., 12 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; dug pits, 18 x 18 x 12 ins., E. & W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth, 2 ft. high, $4\frac{1}{2}$ ft. base over Cor., on N. hillside.	
54.15	Axle canyon, course N. by W. Ascend.	
60.50	Fence brs. N.W. & S.E.	
75.00	Top of ridge falls S. Descend.	
106.90	Porter Gulch, course W. Ascend.	
108.84	Fence brs. N.E. & S.W.	
115.00	Summit of ridge falls N. Descend.	
121.30	Dry gulch- Thos. Porter's house brs. N., 73 lks. dist. Ascend.	