

## Subdivisions, T.1.S., R.33 E., W.M.

Chains		Feet
	<p>Land; mountainous and broken.</p> <p>Soil; stony 4th rate.</p> <p>Good grass, no timber, except aspen in canyon.</p> <p>Whole line passes over mountainous land.</p>	
	<p>N. on line bet. Secs. 29 &amp; 30.</p> <p style="text-align: right;">Var. 19° 15' E.</p> <p>Descend hill.</p>	+300
4.50	A very brushy canyon, course N.W. A cottonwood brs. E.& W. on each side of line, 20 lks. dist. Ascend steep stony hill.	
21.50	Summit of ridge, brs. N.W. & S.E.- Descend.	
40.00	<p>Set basalt stone, 14 x 10 x 8 ins., 10 ins. in ground for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on W. face, and raised mound of stone, 2 ft. high x <math>3\frac{1}{2}</math> ft. base over Cor., from which a lone</p> <p style="padding-left: 40px;">Fir, 11 ins. diam., brs. N.75° E., 204 lks. dist., in a ravine, marked <math>\frac{1}{4}</math> S, B.T.-</p> <p>Pits impracticable.</p>	
63.50	Draw, course N.E. <span style="float: right;">Ascend</span>	
64.30	Summit of ridge, falls N.E. <span style="float: right;">Descend.</span>	
71.70	Deep canyon, course N.W. <span style="float: right;">Ascend.</span>	
80.00	<p>Set basalt stone, 18 x 12 x 5 ins., 12 ins. in ground, for Caraito Secs. 19, 20, 29 &amp; 30, marked, 2 notches on S., and 5 notches on E. edges. Dug pits, 18 x 18 x 12 ins. in each Sec. Cor., <math>5\frac{1}{2}</math> ft. dist. and raised mound of earth and stone, 3 ft. high x <math>4\frac{1}{2}</math> ft. base over Cor. on W. hillside.</p> <p>Soil; stony, 4th rate. Good grass on N. slopes. A few scattering fir and cottonwood in canyons.</p> <p>The whole line runs over mountainous land.</p>	
	<p>E. on random line bet. Secs. 20 &amp; 29.</p> <p style="text-align: right;">Var. 19° 45' E.</p> <p>Ascend.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	