

Subdivisions, T. 1 S., R. 33 E., W.M.

Chains		Feet
80.76	Intersect N. & S. line, 182 lks. S. of Cor. to Secs. 20, 21, 28 & 29. Thence I run, S.88° 42' W. on true line bet. Secs. 20 & 29. Var. 21° 20' E.	
3.76	Summit of ridge falls N.	Descend.
8.26	Head of ravine, course N.	Ascend.
20.26	Summit of hill falls N.W.	Descend
29.76	Canyon, course N.W.	Ascend.
30.76	Trail brs. N.W. & S.E.	
38.51	Summit of ridge falls N.E.	Descend.
40.38	Set basalt stone, 14 x 11 x 8 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; dug pits, 18 x 18 x 12 ins. E. & W. of Cor. $5\frac{1}{2}$ ft. dist., and raised mound of earth and stone, $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., near head of draw. N.E.	440
52.76	Stony summit	Descend
80.76	The Cor. to Secs. 19, 20, 29 & 30. Soil; stony 4th rate. Good grass on N. slopes. No timber. Whole line passes over mountainous land. Sept. 13, 1890.	460
	W. bet. Secs. 19 & 30. Var. 19° 45' E.	
15.03	Gulch, course N.W.	Ascend.
26.64	A basalt stone, in place, 4 x 3 x 2 ft. above the ground.	
31.00	Summit of ridge, falls N.W. N. end of rock cliff, 8 ft. high brs. N. 50° lks. dist. - 32.12 chs.	Descend.
40.00	Set basalt stone, 18 x 18 x 8 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 ins. E. & W. of Cor. $5\frac{1}{2}$ ft. dist., and raised mound of earth and stone, 3 ft. high x $3\frac{1}{2}$ ft. base over Cor., on W. hillside.	
54.50	Stony gulch, course W.	
63.01	Fence brs. N. & S.	
64.75	Canyon, course N.W. Ascend steep hill	-40