

Allotment Subdivisions, T. 1 S., R. 33 E., W.M.
 As surveyed by James P. Currin, U.S. Deputy Surveyor,
 Under Contract No. 537
 Dated March 5, 1889.

Chains		Feet
	<p>The N $\frac{1}{2}$ of the S $\frac{1}{2}$ of SW$\frac{1}{4}$, Sec. 4, included in my instructions, being very steep and broken, not at all arable. I took in its stead the S$\frac{1}{2}$ of S$\frac{1}{2}$ of SE $\frac{1}{4}$ of Sec. 3, containing 40 acres and on those lots are situated a good house, painted and 15 or 20 acres, good growing grain.</p>	
	<p style="text-align: center;"><u>Section 3</u></p> <p>From the Cor. to Secs. 2,3, 10 & 11, which is appest, 4 ins sq., marked T.1 S,R.33 E.,S.11 on S.E.</p> <p style="padding-left: 40px;">S.10 on S.W. face</p> <p style="padding-left: 40px;">S. 2 on N.E. face and</p> <p style="padding-left: 40px;">S. 3 on N.W. face, with 2 notches on E. and 5 notches on S., with pits, 18 x 18 x 12 ins. ,N.E. & W. of post, 5$\frac{1}{2}$ ft. dist. and mound of earth around post.</p> <p>I run</p> <p>N. on true line bet. Secs. 2 & 3.</p> <p style="text-align: right;">Var. 20° E.</p> <p>5.00 Leave grain field.</p> <p>7.00 Road, course E. & W.</p> <p>8.00 McKay Creek, 30 lks. wide, course S.W.</p> <p>10.00 Set stone, 10 x 9 x 8 ins.,7 ins. in the ground for 1/32 Sec. Cor., marked 1/32 on W. face and raised a mound of stone over it, from which,</p> <p style="padding-left: 40px;">A balm, 18 ins. diam.,brs. E. 60 lks. dist.,marked 1/32 S. B.T.</p> <p style="padding-left: 40px;">A balm, 18 ins. diam, brs. N:45° E.,60 lks. dist. marked 1/32 S. B.T.</p> <p>Land in grainfield.</p> <p>Timber in bottom.</p> <p>Soil; 1st rate in field and gravelly in bottom.</p>	
	<p>From the $\frac{1}{4}$ Sec. Cor. on S. Bdy.of Sec.3, which is a basalt stone, 12 x 10 x 8 ins., firmly set in the ground,marked $\frac{1}{4}$ on N. face, with pits, 18 x 18 x 12 ins. N. & S. of Cor., 5$\frac{1}{2}$ ft. dist., and mound of earth alongside.</p> <p>I run,</p>	