

## Allotments, Subdivisions, T. 1 S., R. 33 E., W.M.

Section 3.

Chains		Feet
	N. on true line in Sec. 3.  Var. 19° E.	
4.00	Road, course E. & W.	
8.50	Slough, course W., water in holes.	
10.00	Set stone, 12 x 10 x 8 ins. in mound of stone on bank of creek for 1/32 Sec. Cor., marked 1/32 on W. face and raised a mound of stone over it, from which,  A balm, 6 ins. diam., brs. S. 10° E., 20 lks. dist., marked 1/32 S.B.T.  A balm, 6 ins. diam., brs. S. 15° W., 16 lks. dist., marked 1/32 S. B.T.  Land; level.  Soil; gravelly  Some brush and timber.	
	From the 1/32 Sec. Cor., 10.00 chs. N. of the 1/4 Sec. Cor., bet. Secs. 3 & 10, I run,  E. on random line in Sec. 3.  Var. 19° E.	
20.00	Set temp. 1/32 Sec. Cor.	
40.20	Intersect the E. Bdy. of Sec. 3, 10 lks. N. of 1/32 Sec. Cor. 10 chs. N. of the Cor. to Secs. 2, 3, 10 & 11.  Thence I run,  N. 89° 51' W. on a true line in Sec. 3.  Var. 17° E.	
1.00	McKay Creek, 30 lks. wide, course N.W.  Through timber and brush	
20.10	Set stone, 15 x 10 x 7 ins., 10 ins. in ground for 1/32 Sec. Cor., marked 1/32 on N. face, and raised a mound of stone over it. Pits impracticable.	
40.20	To 1/32 Sec. Cor., 10 chs. N. of 1/4 Sec. Cor. bet. Secs. 3 and 10.  Line down McKay Creek, through brush and timber.  June 24, 1889.	