

South Bdy., T.1 S., R.35 E., W.M.  
 As surveyed by Jacob C. Cooper  
 Under Contract No. 397  
 Dated July 1, 1881.

Chains		Feet
	From the Cor. to Tps. 1 & 2 S., Rs. 35 & 36 E., which is a post marked, T.1 S., S.31 on N.E. R.36 E., S.6 on S.E. T.2 S., S.1 on S.W. and R.35 E., S.36 on N.W. faces from which, A fir, 12 ins. diam., brs. N.64°W., 24 lks. dist., marked T.1 S., R.35 E., S.36, B.T. A pine, 8 ins. diam., brs. S.17°W., 21 lks. dist., marked T.2 S., R.35 E., S.1, B.T. A pine, 8 ins. diam., brs. N.23° E., 35 lks. dist., marked T.1 S., R.36 E., S.31, B.T. A pine, 10 ins. diam., brs. S.65° E., 14 lks. dist., marked T.1 S., R.36 E., S.6, B.T.	
	I run W. on a true line bet. Secs. 1 & 36. Var. 22° E. Ascend through dense timber.	
18.00	Summit of ridge, course N.W. Leave timber and descend.	
20.50	Old emigrant road, course N.W.	
21.00	Enter timber with dense underbrush and fallen timber.	
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, for ¼ Sec. Cor., marked ¼ S., on N. & S. faces, in a marshy sog, from which, A fir, 16 ins. diam., brs. N.48°W., 58 lks. dist., marked ¼ S., B.T. A spruce, 15 ins. diam., brs. S.75°E., 40 lks. dist., marked ¼ S., B.T. Var. 13° 40' E. Ascend through dense timber.	
49.00	Summit of hill; descend through dense buck brush and timber.	
52.75	Ascend through same.	
57.00	Point of ridge; descend.	