

S. Bdy. T. 1 S., R. 35E., W.M.

Chains		Feet
40.00	<p>Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground on top of hill, in dense forest of pine and fir for ¼ Sec. Cor. marked ¼ S. on N. & S. faces, from which,</p> <p>A fir, 14 ins. diam., brs. S.2° W., 7 lks. dist., marked ¼ S., B.T.</p> <p>A pine, 13 ins. diam., brs. N.10° E., 24 lks. dist., marked ¼ S., B.T.</p> <p>Descend.</p> <p style="text-align: right;">Var. 18° 30' E.</p>	
50.00	Ascend through dense forest of pine timber.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, on top of table land, in dense forest, for Cor. to Secs. 3, 4, 33 & 34, marked</p> <p style="padding-left: 40px;">T.1 S., S.34 on N.E.</p> <p style="padding-left: 40px;">R.35 E., S.3 on S.E.</p> <p style="padding-left: 40px;">T.2 S., S.4 on S.W.</p> <p style="padding-left: 40px;">S. 33 on N.W. faces with</p> <p style="padding-left: 40px;">3 notches on E. & W. faces, from which</p> <p>A tamarack, 12 ins. diam., brs. S.60°W., 22 lks. dist., marked T.2 S., R.35 E., S.4, B.T.</p> <p>A fir, 11 ins. diam., brs. S.53°E., 27 lks. dist., marked T.2 S., R.35 E., S.3, B.T.</p> <p>A fir, 16 ins. diam., brs. N.30° W., 14 lks. dist., marked T.1 S., R.35 E., S.33, B.T.</p> <p>A fir, 14 ins. diam., brs. N.11°E., 38 lks. dist., marked T.1 S., R.35 E., S.34, B.T.</p> <p>Land; high, broken and mountainous.</p> <p>Soil; gravelly 4th rate.</p> <p>Timber; pine, fir and tamarack.</p>	
W. on a true line bet. Secs. 33 & 4.		
Var. 20° E.		
Descend through dense timber.		
20.00	Ascend through dense timber.	
32.00	Descend through heavy pine and tamarack, with much dead timber standing.	