

East Bdy., T.1 S., R.35 E., W.M.

Chains		Feet
	I run	
	N. bet. Secs. 31 & 36	
	Var. 22°E.	
	Descend through dense timber and undergrowth.	
34.00	Spring branch, 3 lks. wide, course N.E.; ascend.	
36.50	Center of Foster's toll road, course N.E.	
37.00	Descend through dense timber.	
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, in fir timber and undergrowth for ¼ Sec. Cor., marked ¼ S. on E. & W. faces.	
	A fir, 12 ins. diam., brs. S.54° W., 7 lks. dist., marked ¼ S., B.T.	
	A fir, 13 ins. diam., brs. N.14°E., 7 lks. dist., marked ¼ S., B.T.	
	Descend through heavy pine timber.	
45.00	Ascend in dense thicket of young timber	
57.50	Leave thicket and enter open timber.	
75.00	Summit of mountain ridge, course E. & W. Descend through heavy timber and undergrowth, very dense.	
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, in heavy timber for Cor. to Secs. 25,30,31 and 36, marked	
	T.1 S., S.30 on N.E.	
	R.36, S.31 on S.E.	
	R.35E., S.36 on S.W.	
	S.25 on N.W. faces with	
	1 notch on S. edge and	
	5 notches on N. edge, from which	
	A fir, 24 ins. diam., brs. S.10° W., 26 lks. dist., marked T.1 S., R.35 E., S.36, B.T.	
	A tamarack, 12 ins. diam., brs. S.63° E., 23 lks. dist., marked T.1 S., R.36 E., S.31, B.T.	
	A tamarack, 14 ins. diam., brs. N.22° E., 28 lks. dist., marked T.1 S., R.36 E., S.30., B.T.	
	A fir, 24 ins. diam., brs. N.84°W., 20 lks. dist., marked T.1 S., R.35 E., S.25, B.T.	
	Land; high rolling and mountainous.	