

E. Bdy., T. 1 S., R. 35 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | Descend. | |
| 19.00 | Ravine, course N.W. Ascend. | |
| 40.00 | A pine, 6 ins. diam., which I marked for $\frac{1}{4}$ Sec. Cor., on steep W. hillside, 300 ft. above ravine and 200 ft. below the summit; $\frac{1}{4}$ S. on E. and W. faces, from which, A fir, 12 ins. diam., brs. S.81° W., 20 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. N.81° E., 20 lks. dist., marked $\frac{1}{4}$ S., B.T. | |
| | Descend. | |
| 51.00 | Bottom of canyon, course N.E. | |
| | Ascend. | |
| 58.00 | Ravine, course E. | |
| | Ascend. | |
| 70.00 | Enter timber. | |
| 80.00 | A mound of earth, 5 ft. at base, 2 ft. high, with pits. Set post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in mound on table land, sloping W., in open pine timber, for Cor. to Secs. 1, 6, 7 & 12, marked. T.1 S., S.6 on N.E. R.36 E., S.7 on S.E. R.35 E., S.12 on S.W. and S.1 on N.W. faces, with 5 notches on S. and 1 notch on N. edges, from which, A pine, 30 ins. diam., brs. N.3° E., 75 lks. dist., marked T.1 S., R.36 E., S.6, B.T. A pine, 22 ins. diam., brs. N.62° W., 72 lks. dist., marked T.1 S., R.35 E., S.1, B.T. A pine, 20 ins. diam., brs. S.70° W., 92 lks. dist., marked T.1 S., R.35 E., S.12, B.T. | |
| | Land; high, mountainous and broken. | |
| | Soil; gravelly and rocky, 3rd rate. | |
| | Timber; pine, fir and tamarack. | |