

E. Bdy., T.1 S., R.35 E., W.M.

Chains		Feet
	N. bet. Secs. 1 & 6.	
	Var. 20° E.	
	Descend in open pine timber.	
4.00	Enter young pine timber.	
24.00	Bottom of canyon; course E.	
	Ascend.	
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, on W. of head of ravine, 200 ft. below summit, in pine & fir timber, for ¼ Sec. Cor., marked ¼ S. on E. & W. faces, from which, A fir, 6 ins. diam., brs. S.5° E., 7 lks. dist., marked ¼ S., B.T. A fir, 10 ins. diam., brs. N.32° E., 17 lks. dist., marked ¼ S., B.T.	
	Descend.	
46.00	Bottom of ravine, course S.E. Ascend through young timber and dense underbrush.	
73.50	Intersect Base Line, 26.71 chs. E. of Cor. to Tps. 1, N., Rs. 35 & 36 E. Set post, 4½ ft. long, 4 ins. sq., 24 ins. in ground in heavy timber for Closing Cor. to Tps. 1 S., Rs. 35 & 36 E., marked C.C., T.1 S. on S. R.36 E., S.6 on E. and R.35 E., S.1 on W. faces with 6 notches on S.E. AND W. faces, from which, A fir, 16 ins. diam., brs. S.24° W., 41 lks. dist., marked T.1 S., R.35 E., S.1, B.T. A tamarack, 40 ins. diam., brs. S.74° E., 24 lks. dist., marked T.1 S., R.36 E., S.6, B.T.	
	Land; high mountainous and broken.	
	Soil; rocky, 4th rate.	
	Timber; pine, fir and tamarack.	