

E. Bdy. T. 1 S.; R. 35 E.; W.M.

Chains	<u>General Description.</u>	Feet
	<p>This line runs across the breaks and canyons of the waters on the S. of Meachem Creek and the summits of the ridges are covered with a good quality of pine, fir and tamarack timber.</p> <p>The sides of the mountain are rocky and destitute of timber. Grass good.</p> <p>Water is scarce and very few of the canyons on this line contain streams of water.</p>	
	<p>Subdivisional Lines, T. 1 S., R. 35 E., W.M.            As surveyed by David P. Thompson &amp; Daniel Chaplin,            U.S. Deputy Surveyors,            Under Contract No. 104            Dated April 16th, 1864.</p>	
	<p>I examined the country in this Tp. and found that but a small portion was fit for settlement or cultivation, only two sections on the Creek, which runs through from South to North, could be considered of any value. The remainder of the Tp. is steep and stony, covered with small, scrubby mountain spruce timber.</p> <p>Gold has been found on the creek, but not in quantities to justify miners in working the diggings.</p> <p>Gold quartz has been found in the southern part of the Tp. in detached pieces on the hill sides. One piece was found about three ins. diam., which assayed at the rate of \$5000 per ton, but there has been no regular ledge found, although persons are still engaged in prospecting for it.</p>	
	<p>I commence on the Base Line at Cor. to Secs. 2 &amp; 3 and run S. on a true line bet. Secs. 2 &amp; 3.</p>	
	<p>Var. 19° 30' E.</p>	
.5	Creek, 18 lks. wide, runs N.W.	
4.75	Same creek, 18 lks. wide, runs N.E. Ascend hill.	
40.00	Top of hill, brs. E. & W. Set post for $\frac{1}{4}$ Sec. Cor., from which	