

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
	A pine, 36 ins. diam., brs. N.17° W., 175 lks. dist.	
	A spruce, 12 ins. diam., brs. N.80° E., 49 lks. dist.	
62.00	Emigrant Road brs. E. & W.	
80.00	Set post for Cor. to Secs. 2, 3, 10 & 11, from which,	
	A spruce, 10 ins. diam., brs. N.75°W., 35 lks. dist.	
	A " 15 " " " S.47°W., 68 " "	
	A " 10 " " " S.45°E., 27 " "	
	A " 10 " " " N.32°W., 6 " "	
	Land; rough and broken, stony, 3rd rate.	
	Timber; small spruce and pine	
S. on true line bet. Secs. 10 & 11.		
Var. 19°30' E.		
33.50	Toll road brs. S.E. & N.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., from which,	
	A spruce, 12 ins. diam., brs. N.30°E., 117 lks. dist.	
	A " 12 " " " N.33°W., 35 " "	
80.00	Set post for Cor. to Secs. 10, 11, 14 & 15, from which,	
	A larch, 18 ins. diam., brs. N.8°W., 25 lks. dist.	
	A spruce, 15 " " " N.35°E., 37 " "	
	A " 12 " " " S.35°E., 23 " "	
	A larch, 18 " " " S.15°W., 17 " "	
	Land; rolling, some stony.	
	Soil; 3rd rate.	
	Timber; small spruce, pine and larch.	
W. on a true line bet. Secs. 10 & 15.		
Var. 19° E.		
10.50	Creek, 15 lks. wide, runs N.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., from which,	
	A fir, 10 ins. diam., brs. N.15°W., 29 lks. dist.	
	A larch, 18 " " " S.50°E., 7 " "	
80.00	Set post for Cor. to Secs. 9, 10, 15 & 16, from which,	
	A pine, 4 ins. diam., brs. N.80°W., 16 lks. dist.	
	A " 4 " " " N.60°E., 29 " "	
	A fir, 15 " " " S.35°E., 23 " "	