

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 11 & 12. Var. 20° E.	
28.60	Old road brs. N.W. & E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A tamarack, 3 ins. diam., brs. S.65°E., 29 lks. dist. marked $\frac{1}{4}$ S., B.T. A spruce, 8 ins. diam., brs. N.54°W., 42 lks. dist., marked $\frac{1}{4}$ S., B.T.	
40.20	Dry gulch, course N.E.	
66.00	Dry bed of creek, 5 lks. wide, course N.30° W.	
74.00	Enter opening, brs. N.W. & S.E.	
76.45	Wagon road, brs. N.W. & S.E.	
76.97	Corral fence, brs. N.W. & S.E.	
78.60	" " " E. & W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 1, 2, 11 & 12, marked T.1 S., R.35 E., S.1 on N.E. T.1 S., R.35 E., S.2 on N.W. S.11 on S.W. and S.12 on S.E. faces, with 5 notches on S. and 1 notch on E. edges. from which, A pine, 6 ins. diam., brs. N.45°E., 40 lks. dist., marked T.1 S., R.35 E., S.1, B.T. A pine, 6 ins. diam., brs. N.17°W., 23 lks. dist., marked T.1 S., R.35 E., S.2, B.T. A pine, 22 ins. diam., brs. S.17°W., 41 lks. dist., marked T.1 S., R.35 E., S.11, B.T. A pine, 4 ins. diam., brs. S.13°E., 41 lks. dist., marked T.1 S., R.35 E., S.12, B.T.	
	Land; high and mountainous.	
	Soil; 2nd rate.	
	Heavily timbered with pine, fir and tamarack, 74 chs.	
	Dense undergrowth of pine, fir and tamarack.	