

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains	Feet
	<p>Set basalt stone, 24 x 10 x 3 ins., 18 ins. in ground, for Closing Cor. to Secs. 1 & 12, marked C.C. on W. with 5 notches on S. and 1 notch on N. edges, from which, A pine, 30 ins. diam., brs. N. 42° W., 162 lks. dist., marked C.C., T. 1 S., R. 35 E., S. 1, B. T.</p> <p>Raised a mound of stone alongside. Fits impracticable. Land; high and mountainous.</p> <p>Soil; 2nd and 3rd rate.</p> <p>Heavily timbered with fir, spruce and pine, 89.30 chs. Dense undergrowth of fir, spruce and pine.</p>
	<p>W. on random line bet. Secs. 2 & 11.</p> <p style="text-align: center;">Var. 20° E.</p>
9.00	Old road brs. N.W. & S.E., 100 ft. below Sec. Cor.
9.10	Dry bed of creek, 5 lks. wide, course N.
10.00	Cabin, brs. S., 50 lks. dist.
27.40	Enter opening, brs. N. & S., 100 ft. above bed of creek.
32.40	Leave opening, brs. N. & S.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
63.54	Fence, brs. N. & S.
69.00	Dry gulch, course S.W.
79.92	Intersect N. & S. line, 21 lks. S. of Cor. to Secs. 2, 3, 10 & 11, which is a post, 4 ins. sq., marked
	S. 11 on S.E.
	S. 10 on S.W.
	R. 35 E., T. 1 S., S. 3 on N.W. and
	S. 2 on N.E. faces with
	1 notch on N. and
	2 notches on E. edges,
	from which
	A pine, 22 ins. diam., brs. N. 30° E., 5 lks. dist., marked S. 2, B. T.
	A pine, 24 ins. diam., brs. N. 75° W., 36 lks. dist., marked S. 3, B. T.
	A pine, 22 ins. diam., brs. S. 46° W., 67 lks. dist., marked S. 10, B. T.