

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains

Feet

T.1 N., R.35 E. on N.

S.36 on E.

S.35 on W. faces, with

1 notch on E. and

5 notches on W. edges,

from which,

A tamarack, 12 ins. diam., brs. S.25°W., 18 lks. dist.
marked T.1 S., R.35 E., B.T.

A pine, 12 ins. diam., brs. N.50°W., 36 lks. dist.,
marked T.1 N., R.35 E., S.35, B.T.

A tamarack, 12 ins. diam., brs. N.60°E., 7 lks. dist.,
marked T.1 N., R.35 E., S.36, B.T.

Set post, 4½ ft. long, 4 ins. sq., 24 ins. in ground; for
Closing Cor. to Secs. 1 & 2, marked,

C.C. on S.

T:1 S., R.35 E., S:1 on E.

T:1 S., R.35 E., S:2 on W. faces, with

1 notch on E. and

5 notches on W. edges, 150 ft. above ¼ Sec.

Cor., from which,

A fir, 22 ins. diam., brs. N.46°E., 45 lks. dist.,
marked C.C., T.1 N., R.35 E., S.35, B.T.

A pine, 20 ins. diam., brs. S.34°W., 29 lks. dist.,
marked C.C., T.1 S., R.35 E., S.2, B.T.

A pine, 18 ins. diam., brs. S.72°E., 20 lks. dist.,
marked C.C., T.1 S., R.35 E., S.1, B.T.

Land; high and mountainous.

Soil; 2nd and 3rd rate.

Heavily timbered with pine, fir, tamarack and spruce, 72.88
chains.

Undergrowth of pine, fir, tamarack and spruce.

Oct. 2, 1882.

S. bet. Secs. 13 & 14.

Var. 20° E.

16.00 Top of hill, brs. N.W. & S.E., 150 ft. above Sec. Cor.