

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
39.50	Enter opening and old Migrant Road, brs. N.W. & S.E.	
40.00	Set basalt stone, 20 x 15 x 12 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 18 ins. diam., brs. S.67°E., 77 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 7 ins. diam., brs. N.55°W., 142 lks. dist., marked $\frac{1}{4}$ S., B.T.	
46.65	Old road brs. N.E. & S.W.	
47.00	Leave opening and enter timber, brs. N.W. & S.E.	
62.00	Dry bed of creek, 5 lks. wide, course N.30°W., 100 ft. below $\frac{1}{4}$ Sec. Cor.	
73.00	Enter black pine thicket, brs. N.W. & S.E.	
78.25	Leave black pine thicket, brs. N.E. & S.W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 13, 14, 23 & 24, marked T.1 S., R.35 E., S.13 on N.E. T.1 S., R.35 E., S.14 on N.W. S.23 on S.W. and S.24 on S.E. faces, with 3 notches on S. and 1 notch on E. edges, from which, A pine, 9 ins. diam., brs. N.67°E., 19 lks. dist., marked T.1 S., R.35 E., S.13, B.T. A pine, 12 ins. diam., brs. N.26°W., 25 lks. dist., marked T.1 S., R.35 E., S.14, B.T. A fir, 9 ins. diam., brs. S.61°W., 53 lks. dist., marked T.1 S., R.35 E., S.23, B.T. A fir, 5 ins. diam., brs. S.36°E., 27 lks. dist., marked T.1 S., R.35 E., S.24, B.T.	
	Land; high and mountainous.	
	Soil; 2nd & 3rd rate.	
	Heavily timbered with pine, fir, tamarack and spruce, 76.50 chains.	
	Dense undergrowth of pine, fir, tamarack and spruce and mountain laurel.	