

Subdivisional Lines, T.1S.,R.35 E.,W.M.

Chains	E. bet. Secs. 13 & 24.	Feet
	Var.18°30' E.	
7.70	Dry bed of creek, 3 lks. wide, course N.20°W. And ascend.	
16.40	Old Emigrant road hrs. N.20°W and S.20°E.,150 ft. above bed of creek.	
19.00	Top of hill, hrs. N.& S., 40 ft. above old Emigrant road.	
21.50	Descend hill, hrs. N. & S.	
26.98	Dry bed of creek, 3 lks. wide, course N.,200 ft. below top of hill. And ascend.	
34.00	Top of hill,hrs. N. & S., 250 ft. above bed of creek.	
40.00	Set post, 3 ft. long, 3 ins. sq.,24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A tamarack, 16 ins. diam.,hrs. N.40°W.,13 lks. dist. marked $\frac{1}{4}$ S.,B.T. A fir, 12 ins. diam.,hrs. S.58°E.,31 lks. dist., marked $\frac{1}{4}$ S.,B.T.	
43.00	Descend hill, hrs. N. & S.	
55.00	Enter opening, hrs. N. & S.	
60.00	Leave opening and enter timber,hrs. N. & S.	
67.45	Dry ravine, course S.E., 300 ft. below top of hill and ascend.	
71.00	Enter opening, hrs. N.W. & S.E.	
74.00	Leave opening and enter timber, hrs. N.W. & S.E.	
75.00	Top of hill, hrs. N.W. & S.E., 400 ft. above last ravine.	
77.00	Descend hill, hrs. N. & S.	
83.87	Dry gulch, course S., 300 ft. below top of hill.	
85.50	Enter opening, hrs. N. & S.	
100.90	Leave opening and enter timber,hrs. N. & S.	
102.25	Dry ravine, course S.,100 ft. below last dry gulch.	
105.00	Enter opening, hrs. N. & S.	
108.00	Intersect E. Bdy. of Tp., 564 lks. S. of the Cor. to Secs. 18 & 19, which is a stone, 48 x 34 x24 and post, 4 ins. sq., marked T.1 S.,S.18 on N.E. R.36 E.,S.19 on S.E. R.35 E.,S.24 on S.W. and	