

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	and raised mound of stone alongside. Pits impracticable And descend.	
44.00	Leave opening and enter timber, brs. N. & S.	
64.40	Branch, 3 lks. wide, runs N. 500 ft. below $\frac{1}{2}$ Sec. Cor. Ascend.	
93.20	Enter opening, brs. N.W. & S.E.	
101.20	Leave opening and enter timber, brs. N.20°W & S.20°E.	
108.60	Intersect E.Bdy. of the Tp., 503 lks. S. of the Cor. to Secs. 19 & 30, 550 ft. above Branch, which is a post, 4 ins. sq., marked T.1 S., S.19 on N.E. R.36 E., S.30 on S.E. R.35 E., S.25 on S.W. and S.24 on N.W. faces, with 2 notches on S. and 4 notches on N. edges, from which, A fir, 18 ins. diam., brs. S.81°W., 23 lks. dist., marked T.1 S., R.35 E., S.25, B.T. A tamarack, 16 ins. diam., brs. S.49°E., 25 lks. dist., marked T.1 S., R.36 E., S.30, B.T. A tamarack, 14 ins. diam., brs. N.47°E., 25 lks. dist., marked T.1 S., R.36 E., S.19, B.T. A fir, 16 ins. diam., brs. N.58°W., 15 lks. dist., marked T.1 S., R.35 E., S.24, B.T. Set post, 4 ft. long, 4 ins. sq., for Closing Cor. to Secs. 24 & 25, marked C.C. on W. T.1 S., R.35 E., S.24 on N. T.1 S., R.35 E., S.25 on S. faces with 2 notches on S. and 4 notches on N. edges, from which, A fir, 10 ins. diam., brs. N.40°E., 29 lks. dist., marked, C.C., T.1 S., R.36 E., S.30, B.T.	