

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
	<p>from which,</p> <p>A fir, 8 ins. diam., brs. S.56°E., 10 lks. dist., marked C.C., T.1 S., R.36 E., S.31, B.T.</p> <p>A fir, 4 ins. diam., brs. N.42°W., 25 lks. dist., marked C.C., T.1 S., R.35 E., S.25, B.T.</p> <p>A fir, 7 ins. diam., brs. S.50°W., 24 lks. dist., marked C.C., T.1 S., R.35 E., S.36, B.T.</p> <p>Land; high and mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with fir, spruce, tamarack and pine.</p> <p>Dense undergrowth of fir, tamarack and pine, 97.35 chs.</p>	
	<p>S. bet. Secs. 35 & 36.</p> <p style="text-align: right;">Var. 19°30'E.</p>	
10.00	Enter prairie, brs. N.W. & S.	
10.50	Top of hill, brs. N.W. & S.E., 50 ft. above Sec. Cor.	
12.00	Descend hill, brs. N.W. & S.E.	
27.50	Leave prairie and enter timber, brs. E. & W.	
32.50	Dry gulch, course W.	
38.40	Enter clearing of right of way, brs. N.40°W. & S.35°E.	
39.96	Intersect Railroad Survey, brs. N.40°W. & S.40°E. Location stake No. 297 brs. N.40°W., 14 lks. dist.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., 300 ft. below point of descending hill, marked $\frac{1}{4}$ S. on W. face,	
	<p>from which,</p> <p>A pine, 6 ins. diam., brs. N.70°E., 118 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A pine, 12 ins. diam., brs. S.70°W., 88 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>From this Cor.</p> <p>A pine, 8 ins. diam., brs. S.7°E., 200 lks. dist., marked as the highest point on Mix's Division on the line of the Railroad bet. Meacham's Station and Snake River and 4407 + 57, Cronk's house brs. S.31°E. about 20 chs. from $\frac{1}{4}$ Sec. Cor. and gradually</p>	