

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	below Sec. Cor. and ascend gradually.
6.50	Enter clearing of right of way, brs. N.20°W & S.20°E.
7.42	Intersect Railroad Survey from Umatilla to Baker City, brs. N.20°W. & S.20°E and Location stake No.132 $\frac{1}{4}$ 50 on line.
8.25	Leave clearing of right of way, brs. N.20°W & S.20°E.
11.50	Dry bed of creek, 5 lks. wide, course N.10°W.
12.00	Tie road brs. N.60°W. & S.60°E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 400 ft. above Meacham Creek.
41.75	Enter opening brs. N. & S.
46.50	Top of hill, brs. N.W. & S.E., 20 ft. above $\frac{1}{4}$ Sec. Cor.
47.90	Foster's toll road brs. N.30°W & S.30°E.
52.00	Descend hill, brs. N. & S.
52.60	Leave Opening and enter timber, brs. N. & S.
57.00	Dry ravine, course N., 100 ft. below Foster toll road and ascend.
65.20	Enter opening, brs. N. & S.
67.50	Top of hill, brs. N. & S., 100 ft. above ravine.
70.00	Descend hill, brs. N.W. & S.E.
73.75	Leave opening and enter timber; brs. N. & S.
76.70	Tie road, brs. N.W. & S.E.
79.86	Intersect N. & S. line, 35 lks. W. of the Cor. to Secs.13, 14, 23 & 24, 100 ft. below top of hill.
	Thence I run
	N.89° 45' W. on a true line bet. Secs. 14 & 23.
39.93	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 6 ins. diam., brs. N.47°W., 12 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 6 ins. diam., brs. S.53°W., 44 lks. dist., marked $\frac{1}{4}$ S., B.T.
79.86	The Cor. to Secs. 14, 15, 22 & 23. Land; high and mountainous. Soil; 2nd rate. Heavily timbered with pine, fir and tamarack, 58.71 chs. Dense undergrowth of pine, fir and tamarack.