

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains	Feet
	<p>2 notches on S. and 3 notches on E. edges, from which,</p> <p>A pine, 30 ins. diam., brs. N.37° E., 42 lks. dist., marked T.1 S., R.35 E., S.22,B.T.</p> <p>A pine, 32 ins. diam., brs.N.8°W., 17 lks. dist., marked T.1 S., R.35 E., S.21,B.T.</p> <p>A tamarack, 5 ins. diam., brs.S.43°W,41 lks. dist., marked T.1 S., R.35 E., S.28,B.T.</p> <p>A pine, 26 ins. diam., brs. S.62°E.,41 lks. dist., marked T.1 S., R.35 E., S.27,B.T.</p> <p>Land; high and mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack and spruce.</p> <p>Dense undergrowth of pine, fir, tamarack, spruce and mountain laurel.</p>
	<p>E. on random line bet. Secs. 22 & 27.</p> <p style="text-align: center;">Var. 18°30' E.</p>
19.50	Tie road brs., N. & S.
20.00	Dry bed of creek, 5 lks. wide, in ravine, course N., 300 ft. below Sec. Cor. And ascend.
33.00	Top of hill, brs. N. & S., 500 ft. above bed of creek.
36.00	Descend hill, brs. N. & S.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 50 ft. below top of hill.
59.50	Dry gulch, course N.E., 400 ft. below top of hill.
59;80	Tie road, brs. N.E. & S.W.
67.36	Meacham Creek, 8 lks. wide, course N.20° W., 100 ft. below dry gulch. And ascend.
70.50	Enter clearing of right of way, brs. N.55° W. and S.55°E.
72.30	Intersect Railroad Survey from Umatilla to Baker City, brs. N.55° W., & S.55° E., and Location stake 194 +50 on line.
75.20	Leave clearing for right of way, brs. N.55°W., & S.55° E.
80.00	Intersect N. & S. line, 63 lks. N. of Cor. to Secs. 22, 23, 26 & 27, 175 ft. above Meacham Creek.
	Thence I run,
	N.89° 33' W. on true line bet. Secs. 22 & 27.