

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	Var. 18°30' E.	
40.00	Set basalt stone, 16 x 12 x 6 ins., 11 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 8 ins. diam., brs. N.28°W., 25 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 5 ins. diam., brs. S.20° E., 18 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	The Cor. to Secs. 21, 22, 27 & 28. Land; high and mountainous. Soil; 2nd rate. Heavily timbered with fir, tamarack and pine, 75.30 chs. Dense undergrowth of fir, tamarack, pine and some mountain laurel. Oct. 6th, 1882.	
	W. bet. Secs. 21 & 28. Var. 18°30' E.	
11.00	Top of hill, brs. N.20°W., and S.20° E., 30 ft. above Sec. Cor.	
14.00	Descend hill, brs. N.20°W & S.20° E.	
19.00	Enter opening, brs. N. & S.	
21.50	Leave opening, brs. N. & S.	
30.60	Enter opening, brs. N. & S.	
33.90	Leave opening and enter timber, brs. N. & S.	
37.50	Dry bed of creek, 5 lks. wide in ravine, course N.20°W., 400 ft 400 ft. below top of hill. And ascend.	400 ft
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 100 ft. above bed of creek, marked $\frac{1}{4}$ S. on N. face, from which, A pine, 6 ins. diam., brs. N.50°E., 4 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 5 ins. diam., brs. S.20°W., 20 lks. dist., marked $\frac{1}{4}$ S., B.T. Discontinued line at this $\frac{1}{4}$ Sec. Cor. on account of Uma- tilla Indian Reservation. Land; high and mountainous.	