

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
78.10	<p>I found the Cor. to Secs. 3, 4, 9 & 10, which is a post in mound of stone; .65 lks. E. of line, I found post, marked</p> <p style="padding-left: 40px;">T.1 S., S.3 on N.E.</p> <p style="padding-left: 40px;">S.10 on S.E.</p> <p style="padding-left: 40px;">S.9 on S.W. and</p> <p style="padding-left: 40px;">R.35 E., S.4 on N.W.</p> <p style="padding-left: 40px;">5 notches on S. and</p> <p style="padding-left: 40px;">1 notch on N. edges.</p> <p>I marked bearing trees as follows:</p> <p style="padding-left: 40px;">A pine, 18 ins. diam., brs. N.20° E., 85 lks. dist., marked T.1 S., S.3, B.T.</p> <p style="padding-left: 40px;">A pine, 5 ins. diam., brs. S.72° E., 21 lks. dist., marked S.10, B.T.</p> <p style="padding-left: 40px;">A pine, 5 ins. diam., brs. S.40° W., 45 lks. dist., marked R.35 E., S.9, B.T.</p> <p style="padding-left: 40px;">A pine, 5 ins. diam., brs. N.50° W., 104 lks. dist., marked S.4, B.T.</p> <p>Land; mostly level.</p> <p>Soil; 2nd rate.</p> <p>Heavy pine, fir, spruce and tamarack timber and underbrush</p> <p style="text-align: right;">78.10 chs.</p>	
	<p>E. on random bet. Secs. 3 & 10.</p> <p style="text-align: right;">Var. 23°15' E.</p>	
13.40	To U.R. Bdy., set temp. Cor.	
39.75	<p>To a point 14 lks. N. of $\frac{1}{4}$ Sec. Cor., which I found burned and bearing trees partly destroyed, from thence I</p> <p>Set a post, 30 x 3 x 3 ins., 24 ins. in ground, marked $\frac{1}{4}$ S. on N. face, from which,</p> <p style="padding-left: 40px;">A tamrack, 36 ins. diam., brs. N.45° W., 117 lks. dist. marked $\frac{1}{4}$ S., B.T.</p> <p>Thence I run</p> <p style="padding-left: 40px;">N.89° 48' W. on true line</p>	
2.75	O.S.L.R.R., course N. & S.	
5.25	Meacham Creek, 10 lks. wide, course N.	
26.35	Set post, 48 x 4 x 4 ins., 24 ins. in ground for U.R.M.C.,	