

Subdivisional Lines, T.1 S., R.35 E., W.M.

| Chains | Feet |
|--------|--|
| | And N.20°E., 10.46 chs. dist., from 54½ Mile post on U.R. Bdy. |
| 40.00 | To Cor. to Secs. 20, 21, 28 & 29. Land; rolling, covered with pine, spruce and tamarack timber. Good bunch and pine grass in openings. Soil; 3rd rate. |
| | S. on true line bet. Secs. 28 & 29. Var. 19°E. |
| 20.28 | To U.R.Bdy., 11.55 chs., S.20°W. of 54½ M. post on U.R.Bdy., faced the four sides of a fir tree, 10 ins. diam., for Closing Cor. Marked it U.R.C.C. on N. face. No trees in limits; raised mound of stone alongside of tree Cor. Land; level, covered with scattering pine and fir timber. Good grass. Soil; rocky, 3rd rate. June 30, 1887. |
| | From the Cor. to Secs. 5, 6, 31 & 32 on Base Line, I run, S. bet. Secs. 5 & 6. Var. 19°E. |
| 30.00 | Leave open timber and enter prairie. |
| 39.00 | Set basalt stone, 14 x 12 x 9 ins., 9 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, raised mound of stone alongside. Pits impracticable. |
| 60.00 | Enter thicket. |
| 75.00 | Leave thicket, enter pine opening. |
| 79.00 | Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground, for Cor. to Secs. 5, 6, 7 & 8, marked 5 notches on S. & E. edges, from which, A pine, 18 ins. diam., brs. S.75°E., 13 lks. dist., marked T.1 S., R.35 E., S.8, B.T. A pine, 22 ins. diam., brs. S.84° W., 47 lks. dist., marked S.7, B.T. A pine, 20 ins. diam., brs. N.32°E., 83 lks. dist., |