

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	marked S.5, B.T.	
	No trees in S.6, in limits. Raised mound of stone alongside.	
	Land; rolling, sloping to W. with open pine and brush thickets.	
	Soil; 2nd rate.	
	Dense underbrush, 15 chs.	
	<hr/>	
	E. on random bet. Secs. 5 & 8.	
		Var. 23°30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersect N. & S. line at Cor. to Secs. 4, 5, 8 & 9.	
	Thence I run	
	W. on true line	
40.10	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face, from which,	
	A pine, 5 ins. in diam., brs. N.30°E., 6 lks. dist., marked $\frac{1}{4}$ S.B.T.	
	A pine, 5 ins. diam., brs. S.35°W., 35 lks. dist., marked $\frac{1}{4}$ S., B.T.	
42.20	Wagon road, course N. & S.	
70.00	Enter pine opening.	
80.20	To Cor. to Secs. 5, 6, 7 & 8.	
	Land; rolling, covered with dense thickets of pine, spruce fir and tamarack of all sizes, 70.00 chs.	
	Soil; 3rd rate.	
	<hr/>	
	W. on true line bet. Secs. 6 & 7.	
		Var. 23°30' E.
10.00	Leave pine opening, enter thick timber.	
30.60	Creek, water in holes, course N.W.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face; raised mound of stone alongside.	
46.66	Intersect W. Bdy. of Tp., 4.23 chs. N. of Cor. to Secs. 1 and 12.	
	Set post, 48 x 4 x 4 ins., 2 ft. in ground, for Closing Cor. to Secs. 6 & 7, from which,	