

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	Feet
	<p>A pine, 24 ins. diam., brs. N.75°E., 94 lks. dist., marked T.1 S., R.35 E., S.6, B.T.</p> <p>A pine, 12 ins. diam., brs. S.85°W., 54 lks. dist., marked T.1 S., R.34 E., S.1, B.T.</p> <p>No other trees in limits. Raised-mound of stone alongside. Land; rolling with gradual slope to N.W., covered with pine and fir timber and dense undergrowth, 36.66 chs. Soil: 2nd rate.</p>
	<p>S. bet. Secs. 7 & 8.</p> <p style="text-align: right;">Var. 23° 30' E.</p>
11.00	Leave opening, enter timber.
23.50	Gulch, heavy timber, course N.W.
40.00	<p>Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on W. face, from which,</p> <p>A fir, 16 ins. diam., brs. N.30° E., 55 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A fir, 24 ins. diam., brs. S.60°W., 80 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>
40.60	Indian trail, N.W. & S.E.
80.00	<p>Set post, 48 x 4 x 4 ins., 2 ft. in ground, for Cor. to Secs 7, 8, 17 & 18, marked T.1 S., S.8 on N.E.</p> <p style="padding-left: 40px;">S.7 on N.W.</p> <p style="padding-left: 40px;">S.18 on S.W.</p> <p style="padding-left: 40px;">R.35 E., S.17 on S.E.</p> <p style="padding-left: 40px;">4 notches on S. and</p> <p style="padding-left: 40px;">5 notches on E. edges, from which</p> <p>A pine, 24 ins. diam., brs. N.60°E., 23 lks. dist., marked T.1 S., R.35 E., B.T.</p> <p>A pine, 20 ins. diam., brs. S.45° E., 15 lks. dist., marked S.17, B.T.</p> <p>A pine, 36 ins. diam., brs. S.35° W., 31 lks. dist., marked S.18, B.T.</p> <p>A tamarack, 10 ins. diam., brs. N.55° W., 80 lks. dist. marked S.7, B.T.</p> <p>Land; rolling, covered with heavy pine and tamarack timber</p>