

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	Feet
	<p>marked T.1 S., R.35 E., S.18, C.C., B.T. A pine, 20 ins. diam., brs. S.80° E., 93 lks. dist., marked S.19, C.C., B.T.</p> <p>Land; rolling, covered with heavy fir and tamarack timber with underbrush of same in places, 24.44 chs.</p> <p>Good grass in openings. Soil; 2nd rate, 22.80 chs.</p> <hr/> <p>S, bet. Secs. 19 & 20. Var. 19° E.</p> <p>10.00 Enter pine opening. 30.00 Leave pine opening. 40.00 Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on W. face, from which, A tamarack, 6 ins. diam., brs. S.25° E., 24 lks. dist. marked $\frac{1}{4}$ S., B.T. A tamarack, 8 ins. diam., brs. N.45° W., 5 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>Enter opening.</p> <p>80.00 Set post, 48 x 4 x 4 ins., 2 ft. in ground for Cor. to Secs. 19, 20, 29 & 30, marked T.1 S., S.20 on N.E. S.19 on N.W. R.35 E., S.30 on S.W. S.29 on S.E.</p> <p>Raised mound of stone alongside. Pits impracticable. Land; rolling, covered with scattering pine and tamarack timber; good bunch grass. Soil; 2nd rate.</p> <hr/> <p>E. on random bet. Secs. 20 & 29. Var. 19°15' E.</p> <p>40.00 Set temp. $\frac{1}{4}$ Sec. Cor. 80.00 Intersect N. & S. line at Cor. to Secs. 20, 21, 28 & 29. Thence I run W. on true line</p>