

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	<p>and undergrowth of the same, 58.40 chs.</p> <p>Soil; 3rd rate.</p> <p style="text-align: right;">June 29th, 1887.</p>	
	<p>S. bet. Secs. 8 &amp; 9.</p> <p style="text-align: right;">Var. 21°E.</p>	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for  <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face., from which,  A pine, 10 ins. diam., brs. S.8°W., 140 lks. dist.,  marked <math>\frac{1}{4}</math> S., B.T.  A pine, 20 ins. diam., brs. N.60°E., 239 lks. dist.,  marked <math>\frac{1}{4}</math> S., B.T.</p>	
50.00	Enter pine opening.	
69.00	Draw, course E.	
80.00	<p>Set post for Cor. to Secs. 8, 9, 16 &amp; 17, marked</p> <p style="padding-left: 40px;">S.16 on S.E. face</p> <p style="padding-left: 40px;">S.9 on N.E. "</p> <p style="padding-left: 40px;">S.17 on S.W. "</p> <p style="padding-left: 40px;">S.8, T.1 S., R.35 E. on N.W. face, with  4 notches on S. &amp; E. edges, from which,  A fir, 20 ins. diam., brs. N.65°E., 24 lks. dist.,  marked T.1 S., R.35 E., S.9, B.T.  A fir, 16 ins. diam., brs. S.35°E., 159 lks. dist.,  marked T.1 S., R.35 E., S.16, B.T.  A fir, 24 ins. diam., brs. S.10°W., 130 lks. dist.,  marked T.1 S., R.35 E., S.17, B.T.  A fir, 20 ins. diam., brs. N.70°W., 23 lks. dist.,  marked S.8, T.1 S., R.35 E., B.T.</p> <p>Land; rolling, covered with heavy pine, fir, tamarack tim-  ber and underbrush, 60 chs.</p> <p>Good grass in openings.</p> <p>Soil; 3rd rate.</p>	
	<p>E. on random bet. Secs. 9 &amp; 16.</p> <p style="text-align: right;">Var. 20°E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	