

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	<p>to Secs. 5 &amp; 7, marked</p> <p>C.C. on E.</p> <p>T.1 S., R.35 E., S.6 on N.</p> <p>R.34 E., S.1 on W.</p> <p>S.7 on S. and</p> <p>5 notches on S.</p> <p>1 notch on N. edges, from which,</p> <p>A pine, 24 ins. diam., brs. N.75°E., 94 lks. dist., marked T.1 S., R.35 E., S.6, B.T.</p> <p>A pine, 12 ins. diam., brs. S.85°W., 54 lks. dist., marked T.1 S., R.34 E., S.1, B.T.</p> <p>No other trees in limits; raised stone mound alongside.</p> <p>Land; rolling, covered with pine and fir timber and dense undergrowth, 36.66 chs.</p> <p>Soil; 2nd rate.</p>	
	<p>S. bet. Secs. 7 &amp; 8</p> <p style="text-align: right;">Var. 23° 30' E.</p>	
11.00	Leave opening, enter timber.	
23.50	Gulch, course N.W. Heavy timber	20
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which,</p> <p>A fir, 16 ins. diam., brs. N.30°E., 55 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A fir, 24 ins. diam., brs. S.60°W., 80 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
40.66	Indian trail, N.W. & S.E.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 7, 8, 17 &amp; 18, marked</p> <p>T.1 S., S.8 on N.E.</p> <p>R.35 E., S.17 on S.E.</p> <p>S.7 on N.W.</p> <p>S.18 on S.W. faces,</p> <p>5 notches on E.</p> <p>4 notches on S. edges, from which,</p> <p>A pine, 20 ins. diam., brs. S.45°E., 33 lks. dist.,</p>	