

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	W. on a true line bet. Secs. 18 & 19. Var. 19°E.	
9.80	Indian trail, course S.E.	
22.80	Enter thick timber.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A pine, 5 ins. diam., brs. S.60°E., 45 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 20 ins. diam., brs. N.45°W., 34 lks. dist., marked $\frac{1}{4}$ S., B.T.	
47.24	Intersect Tp. line, 5.29 chs., N. of Cor. to Secs. 13 & 24 of T.1 S., R.34 E. Set a post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 18 & 19, marked T.1 S., R.34 E., S.13 on W. face, T.1 S., R.35 E., S.18 on N.E. S.19 on S. C.C. on E. faces, with 3 notches on N. & S. edges, from which, A pine, 16 ins. diam., brs. N.80°E., 44 lks. dist., marked T.1 S., R.35 E., S.18, B.T. A pine, 20 ins. diam., brs. S.80°E., 50 lks. dist., marked T.1 S., R.35 E., S.19, B.T. And raised mound of stone alongside. Land; rolling, covered with heavy pine, fir and tamarack timber, with underbrush of the same, 24.44 chs. Good grass in openings, 22.80 chs. Soil; 2nd rate.	
	S. bet. Secs. 19 & 20. Var. 19°E.	
10.00	Enter pine opening.	
30.00	Leave " "	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A tamarack, 6 ins. diam., brs. S.25°E., 25 lks. dist.,	