

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
	Scattering pine timber on S. side of canyon. Soil; rocky, 4th rate. Bunch grass on N. side. &	
	E. on true line bet. Secs. 29 & 32. Var. 19°30' E.	
8.47	Gulch, course N.	-200
17.60	Summit, enter timber.	+100
30.75	Creek, 5 lks. wide, course N.	-500
40.00	Set basalt stone, 10 x 10 x 6 ins., 7 ins. in ground, in small glade, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; raised mound of stone around it. Pits impracticable.	+150
59.50	Intersect U.R.Bdy., 5.63 chs. N. 20° E. of 55 $\frac{1}{2}$ M. post. Set basalt stone, 20 x 16 x 8 ins., 15 ins. in ground for Closing Cor. to Secs. 29 & 32, marked U.R., C.C. on W. face; raised stone mound around it. All trees in limits deadened by fire. Pits impracticable. Land; mountainous, 59.50 chs. Line running on steep side of canyon. Pine, fir and tamarack timber. Soil; rocky, 4th rate.	
	W. on true line bet. Secs. 30 & 31. Var. 19°30' E.	
20.30	Canyon, course N.W.	-400
33.00	Summit of point	+300
40.00	Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; raised a stone mound around it. Pits impracticable.	
47.00	Gulch, course N.W.	-150
48.97	Intersect Tp. line, 5.98 chs. N. of Cor. to Secs. 25 & 36, T. 1 S., R. 34 E. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Closing Cor. to Secs. 30 & 31, marked T. 1 S., R. 35 E., S. 30 on N. S. 31 on S.	