

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	<p>T.1 S., R.34 E., S.25 on W. and C.C. on E. faces, with 1 notch on S. and 5 notches on N. edges, from which, A tamarack, 5 ins. diam., brs. N.45°E., 45 lks. dist., marked T.1 S., R.35 E., S.30, B.T. A tamarack, 5 ins. diam., brs. S.20°E., 23 lks. dist., marked T.1 S., R.35 E., S.31, B.T. Raised mound of stone alongside. Land; mountainous, 48.97 chs. Very little timber. Soil; 4th rate.</p>	
	<p>S. on true line bet. Secs. 31 & 32. Var. 19°30' E.</p>	
32.75	Summit of table land, enter timber	+800
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 36 ins. diam., brs. N.30°E., 35 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 30 ins. diam., brs. S.45°W., 45 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>	
85.84	<p>Intersect S. Bdy. of Tp., 9.00 chs. E. of $\frac{1}{4}$ Sec. Cor. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Closing Cor. to Secs. 31 & 32, marked, T.1 S., S.32 on N.E. R.35 E., S.31 on N.W. T.2 S., R.35 E., S.6 on S. C.C. on N. faces, with 5 notches on E. and 1 notch on W. edges, from which, A pine, 10 ins. diam., brs. N.30°E., 54 lks. dist., marked T.1 S., R.35 E., S.32, B.T. A pine, 18 ins. diam., brs. N.85°W., 45 lks. dist., marked T.1 S., R.35 E., S.31, B.T.</p>	
	No other trees in limits; raised mound of stone alongside	