



## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	Feet
	<p>ground, for Closing Cor. of Secs. 6 &amp; 32, with brass cap marked</p> <div style="text-align: center;">  <p>T1S R35E S32 CC ——— S6 T2S R35E 1917</p> </div> <p>from which,</p> <p>A tamarack, 16 ins. diam., brs. N.69°E., 27 lks. dist., (blazes healed over, not opened, old B.T.)</p> <p>A lodgepole pine, 10 ins. diam., brs. S.20°W., 7 lks. dist. (blazes healed over, not opened, old B.T.)</p> <p>A tamarack, 15 ins. diam., brs. N.34°30' W., 40 lks. dist. (blazes healed over, not opened, old B.T.)</p> <p>Thence S.88°46'W., resurveying the N. Bdy. of Sec. 6. Over rolling land, through heavy timber and medium under- growth.</p>
27.62	<p>Intersect line bet. Secs. 31 &amp; 32, T.1 S., R.35 E., 40 lks. S. of the old Closing Cor., which is an old post, 3 x 3 x 30 ins., above ground, marked S.C.C. on S.E., S.31 on N.W. and S.32 on N.E. face; from which the original bearing trees,</p> <p>A pine, 16 ins. diam., brs. N.52°E., 27 lks. dist, (blazes healed over)</p> <p>A pine, 24 ins. diam., brs. N.85°W., 27 lks. dist., marked C.C., T.1 S., R.35 E., S.31, B.T.</p> <p>At the point of intersection Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for Closing Cor. of Secs. 31 and 32, T.1 S., R.35 E., with brass cap, marked</p> <div style="text-align: center;">  <p>T1S R35E CC S31 S32 T2SR35E 1917</p> </div> <p>from which,</p> <p>A pine, 20 ins. diam., brs. N.10°W., 4 lks. dist., marked C.C., T.1 S., R.35 E., S.31, B.T.</p>