

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	Feet
	<p>iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground, for Closing Cor. of Secs. 32 & 33, T.1 S., R.35 E., with brass cap marked</p> <p style="text-align: center;">C. C. T1S R35E <u>S32 S33</u> S5 T2S R35E 1917</p> <p>from which,</p> <p style="padding-left: 40px;">A yellow pine, 30 ins. diam., brs. N.65°W., 83 lks. dist. marked C.C., T.1 S., R.35 E., S.32, B.T.</p> <p style="padding-left: 40px;">A fir, 6 ins. diam., brs. N.22°E., 21 lks. dist., marked C.C., T.1 S., R.35 E., S.33, B.T.</p> <p>Descend 350 ft. to</p>
40.00	<p>Set iron post, 3 ft. long, 1 ins. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor. of Sec. 5 only, with brass cap, marked</p> <p style="text-align: center;"><u>$\frac{1}{4}$S5</u> 1917</p> <p>from which,</p> <p style="padding-left: 40px;">A fir, 14 ins. diam., brs. S.49°W., 159 lks. dist., marked $\frac{1}{4}$ S.5, B.T.</p> <p style="padding-left: 40px;">A basalt rock, 4 x 2 x 2 ft. above ground, brs. E., 2 lks. dist., marked X B.O.</p> <p>Descend 250 ft. to</p>
48.80	Creek, 15 lks. wide, course N.W.; ascend 910 ft. to
74.00	Top of ascent, brs. N.W. & S.E.; over bench land.
77.12	<p>Intersect the Closing Cor. of Tps. 1 & 2 S., R.35 E., on the E.Bdy. of the original Umatilla Indian Reservation, from which the $56\frac{1}{2}$ M. Cor., brs. S.20°W., 4.80 chs. dist.</p> <p>The Closing Cor. is a fir post, 3 ins. sq., 16 ins. above ground, marked T.1 S., S.32 on N.</p> <p style="text-align: center;">C.C., R.35 E. on E. T.2 S., S.5 on S. faces,</p> <p>witnessed as described by the Surveyor-General. I perpetu- ate this Cor., as follows: at the exact Cor. point</p> <p>Set iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground, for Closing Cor. of Tps. 1 & 2 S., R.35 E., with brass cap marked</p>