

N. Bdy., T. 2 S., R. 36 E., W.M.
 As surveyed by John A. Hurlburt, U.S. Deputy Surveyor,
 Under Contract No. 201
 Dated Aug. 5, 1873.

| Chains | | Feet |
|--------|--|-------|
| | East on random on N. Bdy. of Secs. 6, 5, 4, 3, 2, & 1. Var. 21°50'E. Set temp. $\frac{1}{4}$ Sec. and Sec. Cors. at every 40 and 80 chs. & at 5 miles, 78 chs. & 98 lks., Intersect E. Bdy., 28 lks. S. of Cor. to T.1 & 2 S., R. 36 & 37 E. June 14th, 1874. | |
| | N. 89°58'W. on true line on N. Bdy. of Sec. 1 Var. 21°25'E. | |
| 21.00 | Old road runs N. 70°W. | + 10 |
| 40.00 | Set basalt stone, 15 x 10 x 5, 8 ins. in ground for $\frac{1}{4}$ Sec. Cor. | 70 |
| 80.00 | Set pine post, 4 ft. long, 4 ins. sq., 2 ft. in ground for Cor. to Secs. 1, 2, 35 & 36. A fir, 24 ins. diam., brs. N. 55°W., 99 lks. dist. A pine, 8 ins. diam., brs. S. 33°W., 42 lks. dist. A tamarack, 15 ins. diam., brs. S. 54°E., 83 lks. dist. A pine, 10 ins. diam., brs. N. 63°E., 40 lks. dist. | + 30 |
| | Land; rolling. Soil; 2nd rate. A prairie extends 2 or 3 miles N. from the W. $\frac{1}{2}$ of this line. Some scattering pine timber. Fine grass. | |
| | N. 89°58'W. on N. Bdy. of Sec. 2 Var. 19°10'E. | |
| 33.50 | Old road, course N. 60°E. | + 70 |
| 40.00 | Set pine post, 4 ft. long, 3 ins. thick, 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. A pine, 15 ins. diam., brs. N. 14°E., 138 lks. dist. A fir, 20 ins. diam., brs. S. 14°W., 75 lks. dist. Road, 200 lks. S. of $\frac{1}{4}$ Cor. | level |
| 80.00 | Set basalt stone, 20 x 12 x 6, 8 ins. in ground and made stone mound, 2 ft. high for Cor. to Secs. 2, 3, 34 & 35 No trees near. Land; rolling. Soil; 1st & 2nd rate. | |