

Exteriors of T. 1 S., R. 37 E., W.M.

Chains	Feet
	<p>S. 24 on N.W. faces, with 2 notches on S. and 4 notches on N. edges, from which, A pine, 40 ins. diam., brs. N. 80° W., 61 lks. dist., marked T. 1 S., R. 36 E., S. 24, B. T. A pine, 36 ins. diam., brs. S. 40° W., 188 lks. dist., marked T. 1 S., R. 36 E., S. 25, B. T. A pine, 32 ins. diam., grs. S. 3° E., 60 lks. dist., marked T. 1 S., R. 37 E., S. 30, B. T.</p> <p>No other trees in limits and raised mound of stone along- side.</p> <p>Land; mountainous and broken.</p> <p>Soil; rocky, 3rd rate.</p> <p>Timber; pine, fir and tamarack.</p> <p style="text-align: right;">Sept. 9, 1881</p>
	<p>N. bet. Secs. 19 & 24.</p> <p style="text-align: right;">Var. 20° 45' E.</p> <p>On W. mountain side, covered with dead and fallen timber.</p> <p>15.00 Dense undergrowth.</p> <p>19.50 Ascend through dense fallen timber and buckbrush.</p> <p>36.00 Summit of mountain; descend gradually through open and fallen timber.</p> <p>40.00 Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground on W. slope of mountain, 300 ft. below the summit for ¼ Sec. Cor., marked ¼ S. on E. & W. faces, from which, A fir, 11 ins. diam., brs. S. 61° W., 17 lks. dist., marked ¼ S., B. T. A fir, 13 ins. diam., brs. S. 26° E., 29 lks. dist., marked ¼ S., B. T.</p> <p style="text-align: right;">Var. 22° E.</p> <p>Descend through pine timber and fallen logs.</p> <p>70.00 Level glade.</p> <p>78.00 Descend abruptly.</p> <p>80.00 A flat stone, 16 x 16 ins. on steep N. side of mountain, 2000 ft. above bottom of canyon ahead, which I marked</p>