

Exteriors of T.1 S., R.37 E., W.M.

Chains	Feet
	<p>the N.E. side of head of ravine, 1600 ft. above creek, near open timber for Cor. to Secs. 7, 12, 13 & 18, marked</p> <p>T.1 S., S.7 on N.E. R.37 E., S.18 on S.E. R.36 E., S.13 on S.W. and S.12 on N.W. faces, with 4 notches on S. and 2 notches on N. edges, from which, A pine, 28 ins. diam., brs. S.27°W., 66 lks. dist., marked T.1 S., R.36 E., S.13, B.T.</p> <p>Land; high, broken and mountainous. Soil; rocky, 4th rate. Timber, pine, fir and tamarack.</p> <p style="text-align: right;">Sept. 10, 1881</p>
<p>10.00</p> <p>19.50</p> <p>40.00</p> <p>42.00</p> <p>50.00</p> <p>54.00</p> <p>80.00</p>	<p>N. bet. Secs. 7 & 12.</p> <p style="text-align: right;">Var. 21°30'E.</p> <p>Ascend. Enter timber.</p> <p>Dense young timber.</p> <p>A tamarack, 12 ins. diam., on S. side of mountain, 200 ft. below the summit, in dense young timber, which I marked for $\frac{1}{4}$ Sec. Cor., $\frac{1}{4}$ S. on the E. & W. faces, from which, A fir, 6 ins. diam., brs. S.28°E., 14 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. N.78°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>Ledge of rocks.</p> <p style="text-align: right;">Var. 21°E.</p> <p>Leave rocks.</p> <p>Enter timber, black pine and fir.</p> <p>A fir, 5 ins. diam., on table land, in dense timber, which I marked for Cor. to Secs. 1, 6, 7 and 12.</p> <p>T.1 S., S.6 on N.E. R.37 E., S.7 on S.E. R.36 E., S.12 on S.W. and</p>