

## Exteriors of T. 1 S., R.37 E., W.M.

Chains		Feet
52.50	Bed of ravine, course W.	
80.00	<p>Set basalt stone, 16 x 10 x 7 ins., 12 ins. in ground for Cor. to Secs. 19 &amp; 30, marked with 2 notches on S. and 4 on N. edges, from which,</p> <p>A pine, 5 ins. diam., brs. N.47°E., 20 lks. dist. marked T.1 S., S.19, B.T.</p> <p>A pine, 18 ins. diam., brs. S.74°W., 47 lks. dist., marked R.36 E., S. B.T.</p> <p>A pine, 24 ins. diam., brs. S.50°E., 85 lks. dist., marked R.37 E., S.30, B.T.</p> <p>Land; mountainous.</p> <p>Soil; 3rd rate.</p> <p>Timber; pine, fir and tamarack.</p>	
	N. on W. Bdy. of Sec. 19.	
	Var. 20°45'E.	
.50	Ascend.	
10.00	<p>The Cor. to Secs. 24, 25, 19 &amp; 30, which is a post, 4½ ft. long, 4 ins. sq., marked,</p> <p>T.1 S., S.19 on N.E.</p> <p>R.37 E., S.30 on S.E.</p> <p>R.36 E., S.25 on S.W. and</p> <p>S.24 on N.W. faces, from which;</p> <p>A pine, 40 ins. diam., brs. N.80°W., 61 lks. dist., marked T.1 S., R.36 E., S.24, B.T.</p> <p>A pine, 36 ins. diam., brs. S.40°W., 188 lks. dist., marked T.1 S., R.36 E., S.25, B.T.</p> <p>A pine, 32 ins. diam., brs. S.3°E., 60 lks. dist., marked T.1 S., R.37 E., S.30, B.T.</p>	
	Destroyed marks referring to Secs. 19 & 30.	
46.50	Top of hill.	
50.40	The ¼ Sec. Cor.	
80.00	<p>Set basalt stone, 17 x 16 x 7 ins., 12 ins. in ground for Cor. to Secs. 18 &amp; 19, marked with 3 notches on N. &amp; S. edges, from which;</p> <p>A pine, 24 ins. diam., brs. N.53°E., 145 lks. dist.,</p>	