

Exteriors of T. 1 S., 37 E., W.M.

Chains		Feet
	A pine, 7 ins. diam., brs. S.80°E., 7 lks. dist., marked T.1 S., R.37 E., S.7, B.T.	
	A pine, 4 ins. diam., brs. N.45°E., 5 lks. dist., marked T.1 S., R.37 E., S.6, B.T.	
	A pine, 12 ins. diam., brs. S.66°W., 15 lks. dist., marked T.1 S., R.36 E., S.12, B.T.	
	A pine, 10 ins. diam., brs. N.19°W., 21 lks. dist., marked T.1 S., R.36 E., S.1, B.T.	
52.00	Brook, 2 lks. wide, uns E.	
53.00	The $\frac{1}{2}$ Sec. Cor.	
88.20	The Closing Cor. to Tps. 1 S., Rs. 36 & 37 E., which is a post, 4 ins. sq., set firmly in ground, marked C.C., T.1 S. on S. R.37 E., S.6 on E. R.36 E., S.1 on W. faces, with 6 notches on S.E. & W. faces, from which, A tamarack, 20 ins. diam., brs. S.65°W., 17 lks. dist. marked T.1 S., R.36 E., S.1, B.T. A tamarack, 13 ins. diam., brs. S.41°E., 35 lks. dist. marked T.1 S., R.37 E., S.6, B.T.	
	Land; mountainous.	
	Soil; 3rd rate.	
	Heavy pine, fir and tamarack timber.	
	Undergrowth of pine and fir.	

	Sept. 19, 1882.	
	General Description.	
	The land in this Tp. is generally hilly and mountainous, covered with heavy pine, fir, tamarack and spruce timber of good quality, and the Tp. being convenient to settlements, makes it valuable on account of its timber.	
	It should be subdivided.	