

## Subdivisional Lines, T. 1 S. R. 36 E., W.M.

Chains		Feet
	<p>Thence I run N.89°54'W. on a true line bet. Secs. 25 &amp; 36</p> <p>40.36 Set a basalt stone, 15 x 8 x 8 ins., 10 ins. in ground for ¼ Sec. Cor., marked ¼ on N. face and raised mound of stone alongside.</p> <p>80.72 The Cor. to Secs. 25, 26, 35 &amp; 36. Land; mountainous. Soil; sandy loam, 2nd rate. Timber; scattering fir, pine and tamarack, with a dense undergrowth of mahogany and buck brush.</p>	
	<p>N. bet. Secs. 25 &amp; 26. Var. 18½°E.</p> <p>Descend about 400 ft. to</p> <p>30.50 Dry bed of creek, course N.W. Thence descending along steep side of hill.</p> <p>40.00 Set basalt stone, 12 x 12 x 6 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, and raised mound of stone alongside.</p> <p>80.00 Set basalt stone, 16 x 9 x 4 ins., 11 ins. in ground, for Cor. to Secs. 23, 24, 25 &amp; 26, marked with 2 notches on S. and 1 notch on E. edges, from which, A fir, 5 ins. diam., brs. S.20°W., 150 lks. dist., marked T.1 S., R.36 E., S.26, B.T. A fir, 14 ins. diam., brs. N.85°W., 150 lks. dist., marked T.1 S., R.36 E., S.23, B.T. no other trees within limits and raised mound of stone alongside. Land; mountainous. Soil; sandy loam and stony, 2nd &amp; 3rd rate. Timber; scattering fir, pine and tamarack, with dense undergrowth of mahogany and buck brush.</p>	
	<p>E. on random line bet. Secs. 24 &amp; 25. Var. 18°E. Ascend.</p>	