

Subdivisional Lines, T. 1 S., R. 36 E., W.M.

Chains		Feet
80.78	<p>alongside.</p> <p>The Cor. to Secs. 2, 3, 10 & 11.</p> <p>Land; mountainous.</p> <p>Soil; sandy loam, 2nd rate.</p> <p>Timber; sacttering fir and pine.</p> <p style="text-align: right;">Oct. 19, 1882.</p>	
40.00	<p>N. bet. Secs. 2 & 3</p> <p style="text-align: right;">Var. 18°E.</p> <p>Descend along steep side hill.</p> <p>Set basalt stone, 15 x 10 x 5 ins., 10 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, and raised mound of stone alongside.</p>	
47.00	Meacham creek, nearly dry, course N.	
52.00	Leave creek, course N.E.	
74.50	<p>Intersect the Base Line at a point, 20.34 chs. E. of the Cor. to Secs. 34 & 35, T. 1 N., R. 36 E.</p> <p>Set basalt stone, 14 x 12 x 4 ins., 9 ins. in ground for Closing Cor. to Secs. 2 & 3, marked C.C., with 2 notches on E. and 4 notches on W. edges, from which,</p> <p style="padding-left: 40px;">A pine, 20 ins. diam., brs. S. 20° E., 144 lks. dist., marked T. 1 S., R. 36 E., S. 2, B. T.</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., brs. S. 20° W., 30 lks., dist. marked T. 1 S., R. 36 E., S. 3, B. T.</p> <p>No other tree within limits and raised mound of stone alongside.</p> <p>Land; mountainous. on S. 47.00 chs., remainder level.</p> <p>Soil; sandy loam and stony, 2nd & 3rd rate.</p> <p>Timber; scattering fir and pine.</p>	
	<p>From the Cor. to Secs. 3, 4, 33 & 34 on the S. Bdy., which is a basalt stone, 18 x 14 x 5 ins., with 3 notches on E. & W. edges, with mound of stone alongside.</p> <p>I run</p> <p>N. bet. Secs. 33 & 34</p> <p style="text-align: right;">Var. 20° E.</p>	