

Subdivisional Lines, T.1 S., R.36 E., W.M.

| Chains | | Feet |
|---------------------------------------|---|------|
| | A fir, 30 ins. diam., brs. S.25°W., 120 lks. dist., marked T.1 S., R.36 E., S.21, B.T. | |
| | A fir, 14 ins. diam., brs. N.65°W., 145 lks. dist., marked T.1 S., R.36 E., S.16, B.T. | |
| | Land; rolling and mountainous. | |
| | Soil; sandy loam, 2nd rate. | |
| | Heavily timbered with black pine, fir and tamarack. | |
| E. on random line bet. Secs. 15 & 22. | | |
| Var. 20°E. | | |
| 1.00 | Top of ridge, course N.E. | |
| 10.00 | A gulch, about 100 ft. below ridge, course N.E. | |
| 18.00 | A ridge, about 75 ft. above gulch, course N.E. | |
| 28.50 | A gulch, about 75 ft. below ridge, course N. | |
| 38.50 | A ridge, about 75 ft. above gulch, course N. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 48.50 | A gulch, about 100 ft. below ridge, course N. | |
| 67.00 | A ridge, about 75 ft. above gulch, course N. | |
| 72.00 | A gulch, about 75 ft. below ridge, course N. | |
| 80.72 | Intersect, 8 lks. N. of the Cor. to Secs. 14, 15, 22 & 23 Thence I run N. 89° 57' W. on a true line bet. Secs. 15 & 22. | |
| 40.36 | Set basalt stone, 11 x 10 x 5 ins., 7 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A fir, 14 ins. diam., brs. N. 8°E., 79 lks. dist., marked $\frac{1}{4}$ S., B.T. | |
| | No other tree within limits and raised a mound of stone alongside. | |
| 80.72 | The Cor. to Secs. 15, 16, 21 & 22. Land; mountainous. Soil; sandy loam and stony, 2nd & 3rd rate. Heavily timbered with pine, fir and tamarack. | |
| N. bet. Secs. 15 & 16. | | |
| Var. 20°E. | | |
| | Descend through timber. | |