

Subdivisional Lines, T.1 S., R.36 E., W.M.

Chains		Feet
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S., on W. face, from which, A fir, 14 ins. diam., brs. S.80°E., 22 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 16 ins. diam., brs. S.84°W., 11 lks. dist., marked $\frac{1}{4}$ S., B.T.	
40.75	Wagon road, course E. & W.	
41.50	Bottom of canyon about 800 ft. below Sec. Cor.; dry bed of Meacham creek, 100 lks. wide, course E.	
43.40	Intersect Baker City branch of O.R. & N.Co.'s Railway line.	
45.00	Leave heavy and enter scattering timber.	
78.00	Top of ridge, about 600 ft. above creek, course S.W.	
80.00	Set basalt stone, 16 x 8 x 4 ins., 11 ins. in ground for Cor. to Secs. 9, 10, 15 & 16, marked with 4 notches on S. and 3 notches on E. edges, from which, A pine, 22 ins. diam., brs. N.35°E., 75 lks. dist., marked T.1 S., R.36 E., S.10, B.T. A pine, 12 ins. diam., brs. S.35°W., 152 lks. dist., marked T.1 S., R.36 E., S.16, B.T. A fir, 6 ins. diam., brs. N.58°W., 152 lks. dist., marked T.1 S., R.36 E., S.9, B.T.	
	No other tree in limits and raise mound of stone alongside.	
	Land; mountainous.	
	Soil; sandy loam and stone, 2nd & 3rd rate.	
	Heavily timbered with fir and pine on S.45.00 chs., scattering timber on remainder.	
	E. on random line bet. Secs. 10 & 15.	
	Var. 21°E.	
	Over rough mountainous land.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.62	Intersect, 54 lks. S. of the Cor. to Secs. 10, 11, 14 & 15. Thence I run S.89°37' W. on a true line bet. Secs. 10 & 15.	
40.31	Set basalt stone, 15 x 8 x 8 ins., 10 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face,	