

## Subdivisional Lines, T.1 S., R.36 E., W.M.

| Chains | E. on random line bet. Secs. 29 & 32.                                    | Feet |
|--------|--|------|
|        | Var. $20\frac{1}{2}^{\circ}$ E.  |      |
|        | Through timber.  |      |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. Cor.  |      |
| 80.74  | Intersect, 15 lks. N. of Cor. to Secs. 28, 29, 32 & 33.                  |      |
|        | Thence I run   |      |
|        | N. $89^{\circ}54'$ W. on a true line bet. Secs. 29 & 32.                 |      |
| 40.37  | Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for                  |      |
|        | $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, |      |
|        | A fir, 8 ins. diam., brs. $15^{\circ}$ E., 43 lks. dist.,                |      |
|        | marked $\frac{1}{4}$ S., B.T.  |      |
|        | A fir, 10 ins. diam., brs. S. $60^{\circ}$ W., 60 lks. dist.,            |      |
|        | marked $\frac{1}{4}$ S., B.T.  |      |
| 80.74  | The Cor. to Secs. 29, 30, 31 & 32.                                       |      |
|        | Land; mountainous.   |      |
|        | Soil; sandy loam, 2nd rate.  |      |
|        | Heavily timbered with fir, tamarack and pine. Dense under-               |      |
|        | growth of fir, pine, tamarack and mountain laurel.                       |      |
| <hr/>  |  |      |
|        | W. on a random line bet. Secs. 30 & 31.                                  |      |
|        | Var. $20\frac{1}{2}^{\circ}$ E.  |      |
|        | Through timber.  |      |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. Cor.  |      |
| 73.00  | Wagon road, course N.W.  |      |
| 79.72  | Intersect W. Bdy., 56 lks. N. of Cor. to Secs. 30, 31, 25 &              |      |
|        | 36, which is a post, 4 ins. sq., marked,                                 |      |
|        | T.1 S., S.30 on N.E.   |      |
|        | R.36 E., S.31 on S.E.  |      |
|        | R.35 E., S.36 on S.W. and  |      |
|        | S.25 on N.W. faces, with   |      |
|        | 1 notch on S. and  |      |
|        | 5 notches on N. edges, from which,                                       |      |
|        | A fir, 24 ins. diam., brs. S. $10^{\circ}$ W., 26 lks. dist.,            |      |
|        | marked T.1 S., R.35 E., S.36, B.T.                                       |      |
|        | A tamarack, 12 ins. diam., brs. S. $63^{\circ}$ E., 23 lks. dist.,       |      |
|        | marked T.1 S., R.36 E., S.31, B.T.                                       |      |