

Subdivisional Lines, T.1 S., R.36 E., W.M.

Chains		Feet
	marked $\frac{1}{4}$ S., B.T.	
80.50	The Cor. to Secs. 7, 8, 17 & 18. Land; mountainous. Soil; sandy loam, 2nd rate. Heavily timbered with fir, pine and tamarack. Oct. 27, 1882	
	T	
	N. bet. Secs. 7 & 8. Var. $19\frac{1}{2}^{\circ}$ E.	
	Ascend about 400 ft. to	
20.00	Summit of ridge, course E.	
40.00	Set basalt stone, 12 x 9 x 5 ins., 8 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 4 ins. diam., brs. N.40°E., 16 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 12 ins. diam., brs. S.45°W., 75 lks. dist., marked $\frac{1}{4}$ S., B.T.	
67.50	Bottom of gulch about 600 ft. below ridge; dry bed of creek course E. Ascend about 250 ft. to	
80.00	Set basalt stone, 22 x 6 x 5 ins., 16 ins. in ground, for Cor. to Secs. 5, 6, 7 & 8, marked with 5 notches on S. and E. edges, from which, A pine, 22 ins. diam., brs. N.16°E., 200 lks. dist., marked T.1 S., R.36 E., S.5, B.T. A pine, 24 ins. diam., brs. S.85°W., 188 lks. dist., marked T.1 S., R.36 E., S.7, B.T. A pine, 10 ins. diam., brs. N.10°W., 83 lks. dist., marked T.1 S., R.36 E., S.6, B.T.	
	Land; mountainous. Soil; stony, 3rd rate. Heavily timbered with fir, tamarack and pine.	
	E. on a random line bet. Secs. 5 & 8. Var. $19\frac{1}{2}^{\circ}$ E.	
	Descend about 400 ft. to	
17.00	Foot of hill, course S.E.	
18.50	Wagon road, course S.	