

West Bdy. of Tp. 1 S., R. 38 E., W.M.  
 As surveyed by Timothy W. Davenport, U.S. Deputy surveyor,  
 Under Contract No. 102,  
 Dated July, 20th, 1863.

Chains		Feet
	N. bet. Secs. 25 & 30.	
	Var. 21°30'E.	
80.00	Set post Cor. to Secs. 19, 30, 24 & 25, from which A white fir, 16 ins. diam., brs. N.50°W., 24 lks. dist. A " " 30 " " " S.8°W., 58 " " A " " 8 " " " S.60°E., 44 " "	
	N. bet. Secs. 19 & 24	
	Var. 18°30'E.	
40.00	Set 1/4 Sec. Cor. on the N. side of steep and deep canyon, or ravine, from post; A White fir, 12 ins. diam., brs. S.80°W., 15 lks. dist. A " " 12 " " " N.30°E., 16 " "	500
44.50	Bottom of ravine, creek, 15 lks. wide, runs N.W.	200
80.00	Set post Cor. to Secs. 18, 19, 13 & 24, from which White fir, 8 ins. diam., brs. S.80°W., 19 lks. dist.; " " 8 " " " N.20°W., 18 " " " " 12 " " " N.58°E., 40 " " Surface of this mile is broken by ridges of mountains.	300
	N. bet. Secs. 13 & 18.	
	Var. 21°15'E.	
40.00	Set 1/4 Sec. post on N. side of ridge, from which, A white fir, 5 ins. diam., brs. W., 2 lks. dist., A " " 6 " " " N.85°E., 11 lks. dist.	
80.00	Set post Cor. to Secs. 7, 18, 12 & 13 in the bottom of ravine, from which post, A white fir, 8 ins. diam., brs. S.40°W., 23 lks. dist. A " " 30 " " " S.30°E., 45 " " A " " 5 " " " N.80°W., 16 " "	400
	N. bet. Secs. 7 & 12.	
	Var. 20°E.	
35.00	Bottom of ravine, branch, 12 lks., runs W.	800
40.00	Set 1/4 Sec. Post, from which, A white fir, 7 ins. diam., brs. S.50°W., 10 lks. dist. A " " 5 " " " East, 4 " "	200