

West Bdy. of Tp. 1 S., R. 38 E., W.M.

Chains		Feet
70.00	Top of ridge	300
80.00	Set post Cor. to Secs. 6, 7, 1 & 12 on the N. side of ridge, from which post, <ul style="list-style-type: none"> A white fir, 14 ins. diam., brs. N. 55° W., 15 lks. dist. A " " 8 " " " S. 55° W., 26 lks. dist. A hemlock, 16 " " " N. E. 22 " " A white fir, 5 " " " S. 32° E., 38 " " 	250
N. bet. Secs. 1 & 6		
Var. 20° E.		
11.00	Branch, 12 lks. wide, runs W.	400
40.00	Set $\frac{1}{4}$ Sec. post on top of ridge, from which post, <ul style="list-style-type: none"> A white fir, 6 ins. diam., brs. N. 60° W., 62 lks. dist. A " " 6 " " " S. 85° E., 135 " " 	600
81.00	Intersect Base Line, 7.96 chs., E. of Tp. Cor. bet. T. 1 N., R. 37 & 38 E. <ul style="list-style-type: none"> Set post Cor. to Tps. 1 S., Rs. 37 & 38 E., from which, <ul style="list-style-type: none"> A spruce, 8 ins. diam., brs. N. 40° W., 25 lks. dist. A " 8 " " " N. 60° E., 24 " " A " 16 " " " S. 30° W., 78 " " A " 8 " " " S. 30° E., 48 " " 	
Var. 20° E.		
Sept. 18, 1863.		
Exteriors of T. 1 S., R. 37 E., W.M. As surveyed by Jacob C. Cooper, U.S. Deputy Sur. Under Contract No. 397 Dated July 1, 1881		
W. on a true line bet. Secs. 5 & 32		
Var. 21° E.		
Descend gradually through open pine timber.		
10.00	Touch Fox's Hill road on N. end of bridge; a ravine, course S. E.; ascend through dense brush.	
20.00	Summit. Level open pine timber.	
40.00	Set post, 3 $\frac{1}{2}$ ft. long, 3 ins. sq., 18 ins. in ground on S. slope of hill, in open timber, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. & S. faces, from which,	