

## Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	<p>Heavily timbered with pine and fir. Dense fir and pine undergrowth.</p> <p>*****</p> <p>Sept. 22, 1882.</p>	
	<p>N. bet. Secs. 14 &amp; 15</p> <p>Var. 18°15'E.</p> <p>Ascend Butte from Cor.</p>	
35.00	Top of Round Butte, 1000 ft. above Sec. Cor. and descend gradually.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which,</p> <p>A tamarack, 12 ins. diam., brs. N.48°E., 20 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A fir, 4 ins. diam., brs. N.48°W., 10 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
79.00	Spring on line, runs N.E.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 10, 11, 14 &amp; 15, marked</p> <p>T.1 S., S.11 on N.E.</p> <p>R.37 E., S.10 on N.W.</p> <p>S.14 on S.E. and</p> <p>S.15 on S.W. with 4 notches on S. and 2 on E. edges, from which,</p> <p>A fir, 5 ins. diam., brs. S.50°E., 6 lks. dist., marked T.1 S., S.14, B.T.</p> <p>A fir, 12 ins. diam., brs. N.43°E., 31 lks. dist., marked T.1 S., S.11, B.T.</p> <p>A fir, 15 ins. diam., brs. N.30°W., 37 lks. dist., marked T.1 S., R.37 E., S.10, B.T.</p> <p>A fir, 4 ins. diam., brs. S.52°W., 43 lks. dist., marked S.15, B.T., 400 ft. below top of Butte.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack.</p> <p><u>Dense fir, whortle berry, pine and willow undergrowth.</u></p>	