

Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	<p>marked S.20, B.T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine and fir.</p> <p>Dense groves of pine and fir undergrowth.</p>	
	<p>E. on random line bet. Secs. 16 &amp; 21.</p> <p>Descend. Var. 18°15'E.</p>	
10.00	Ravine, course N. 100 ft. below Sec. Cor.	
21.00	Enter bottom, brs. N. & S.	
27.00	Dry bed of creek; course S.	
30.00	Leave bottom and gradual ascent.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. & S. line, 21 lks. S. of Cor. to Secs. 15, 16, 21 & 22, 200 ft. above $\frac{1}{4}$ Sec. Cor.	
	Thence I run	
	S.89°51'W. on true line bet. Secs. 16 & 21.	
39.90	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which;	
	A pine, 30 ins. diam., brs. N.27°W., 11 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	A fir, 18 ins. diam., brs. S.30°E., 12 lks. dist., marked $\frac{1}{4}$ S., B.T.	
79.80	The Cor. to Secs. 16, 17, 20 & 21.	
	Land; rolling.	
	Soil; 1st rate.	
	Heavily timbered with pine, fir and tamarack.	
	Dense undergrowth of pine and fir.	
	N. bet. Secs. 16 & 17.	
	Var. 16°15'E.	
	Descend along hillside.	
15.00	Ravine; course N.E., 200 ft. below Sec. Cor.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which;	
	A fir, 12 ins. diam., brs. S.88°W., 29 lks. dist.,	