

Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	<p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack.</p> <p>Dense fir, pine, willow and laurel undergrowth.</p>	
	<p>E. on random line bet. Secs, 29 & 32.</p> <p style="text-align: right;">Var. 23°E.</p> <p>Ascend along S. side of Butte.</p>	
10.00	Begin to descend.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 350 ft. below Sec. Cor.	
80.00	Intersect N. & S. line, 70 lks. N. of Cor. to Secs. 28, 29, 32 & 33.	
	Thence I run	
	N. 89°30'W. on true line bet. Secs. 29 & 32.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, 500 ft. above Sec. Cor., from which;	
	<p>A tamarack, 15 ins. diam., brs. S.50°E., 24 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A tamarack, 15 ins. diam., brs. N.74°E., 23 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>	
80.00	The Cor. to Secs. 29, 30, 31 & 32.	
	<p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine and fir.</p> <p>Dense undergrowth of fir, pine and laurel.</p>	
	<p>W. on random line bet. Secs. 30 & 31.</p> <p>Descend. Var. 23°E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 500 ft. below Sec. Cor. at foot of Butte, brs. N. & S. and gradual descent to	
88.95	Intersect W. Bdy. of Tp. at Cor. to Secs. 30 & 31, which is a basalt stone, 18 x 8 x 7 ins., marked with 1 notch on S. and 5 on N. edges, from which;	
	A pine, 12 ins. diam., brs. S.33°E., 76 lks. dist., marked R.37 E., S.31, B.T.	